

Diagram No. 1247

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

## DESCRIPTIVE REPORT

(HYDROGRAPHIC)

Type of Survey ... Wire Drag.
Field No. ... RH-20-2-73
Office No. ... FE-213WD (1973)

LOCALITY

State ... Florida

General Locality . Fort Pierce
Locality ... Off St. Lucie Shoal

19 73
CHIEF OF PARTY
CDR L.E. Pickens

LIBRARY & ARCHIVES

November 20, 1974

☆ U.S. GOV. PRINTING OFFICE: 1976-669-441

NOTE: A new system for registering Field Examinations (FE's) was established in 1980. All FE's are now consecutively numbered as shown hereon. The date shown in the new format is the actual date of survey. This material was previously registered as;

FE No.2 1974WD

FE 213

# FENo.2 1974 FE 213 WD

FORM C&GS-504

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY

## DESCRIPTIVE REPORT

Type of Survey WIRE DRAG

Field No. RH-20-2-73 Office No. SP-AMC-1-RH-73

#### LOCALITY

State FLORDIA

General locality FORT PIERCE

Locality OFF ST. LUCIE SHOAL

19.73

CHIEF OF PARTY

CDR.LEONARD E.PICKENS

LIBRARY & ARCHIVES

11-20-74 DATE

FORM C&GS-537

## U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY

REGISTER NO.

#### **HYDROGRAPHIC TITLE SHEET**

#-9368 SP-AMC-1-RH-73

INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.


FIELD NO.

RH-20-2-73

State Florida
General locality Fort Pierce
Locality Off St. Lucie Shoal
Scale 1:20,000 Date of survey 19 thru 28 March 1973
Instructions dated 15 January thru 22 Feb. 1973 Project No. SP-AMC-1-R/H-73
Vessel NOAA Ships RUDE & HECK
Chief of party CDR LEONARD E. PICKENS
Surveyed by Ships Personnel
Soundings taken by echo sounder, hand lead, xsotax
Graphic record scaled by
Graphic record checked by
Protracted by CALCOMP AMC Automated plot by AMC
Soundings penciled by M.W. Johnson AMC
Soundings in Machines feet at MLW MIXEW BASED ON PRESECTED TIDES
<b>i</b>
REMARKS: Ship and FEN Buoys plotted by automation
all other work done manually

#### TABLE OF CONTENTS


- I. SHEET LAYOUT
- II. PROGRESS SKETCH
- III. A) AUTHORITY
  - B) CHARACTER & LIMITS OF THE WORK
  - C) CONTROL & SHORELINE
  - D) DATE OF SURVEY
  - E) TIDAL REDUCERS
  - F) JUNCTIONS
  - G) SPLITS
  - H) GROUNDINGS & HANGS
  - I) GENERAL NOTES
  - J) CURRENTS
  - K) DISCREPANCIES & COMPARISONS WITH RECENT SURVEYS & CHARTS
  - L) PERSONNEL & EQUIPMENT
  - M) MISCELLANEOUS
  - N) SUMMARY
  - O) RECOMMENDATIONS
  - P) APPROVAL
- IV. LIST OF ATTACHMENTS



PROGRESS SKETCH

80 00

80, 10



OPR-SP-AMC-1-R/H-73

WIRE DRAG- SHEET 20-2-73

FORT PIERCE, FLORIDA


NOAA SHIPS RUDE & HECK


L.E.PICKENS, CHIEF OF PARTY

MARCH 1973

SCALE 1:80,000

80,05





27 20

#### DESCRIPTIVE REPORT

TO ACCOMPANY

WIRE DRAG FIELD NUMBER RH-20-2-73

PROJECT SP-AMC-1-R/H-73

FORT PIERCE, FLORIDA

1973

CDR L.E. PICKENS

NOAA SHIPS RUDE & HECK

#### A. AUTHORITY ,

This project was authorized under Project Instructions SP-AMC-1-R/H-73, Wire Drag, Southeast Coast Investigations, dated 15 January 1973; also, Change 1, dated 9 February 1973, Change 3, dated 14 February 1973, and Change 3, dated 22 February 1973.

#### B. CHARACTER AND LIMITS OF THE WORK

The purpose of this project was to investigate and prove or disprove the existence of three reported items offshore of Fort Pierce, Florida.

The locality of the survey, covered by C&GS Charts 1247 and 1112 is as follows: Sheet layout is from Latitude 27°19'N to 27°27'N and from Longitude 80°03'W to 80°16'W.

The reported positions of the three items are as follows: Item B-1

This item not investigated

Latitude 27°23.6'N, Longitude 80°03.1'W; Item B-2 Latitude 27°23.0'N,

Longitude 80°08.0'W; Item B-3 Latitude 27°20.2'N, Longitude 80°04.6'W.

Bol (Wreck Amazone)

The entire survey was conducted on a scale of 1:20,000 using Raydist DR-S Range-Range control.

#### C. CONTROL AND SHORELINE

Raydist DR-S Range-Range control was utilized. The Raydist was operating on a frequency of 3300.4 KHz, giving a lane width of 45.39904 meters.

There was no shoreline on the sheet.

Two Raydist shore stations, FAT and WORTH, were utilized for control.

FAT, located 6.7 miles north of the Fort Pierce, Florida entrance channel, served as the RED station. WORTH, located near Jupiter Inlet, Florida, served as the GREEN station.

Upon completion of the survey the stations were dismantled, but both stations are recoverable as described in the enclosed station descriptions under attachment VII. A list of all signals used is given in Attachment I.

#### D. DATE OF SURVEY

Operations on SP-AMC-1-R/H-73 (Sheet R/H-20-2-73) were begun on 19 March 1973 and completed on 28 March 1973.

#### E. TIDAL REDUCERS

Preliminary reduction of each days data was done using predicted tides.

Actual tidal data has been furnished by the Rockville Office for the standard tide gauge at Miami Beach, Florida with correctors for Fort

Pierce, Florida. See Attachment X for description and location of tide gauge station.

Servicing and levels to this gauge were not required.

#### F. JUNCTIONS

Not applicable.

#### G. SPLITS

No splits exist on Sheet R/H-20-2-73.

#### H. GROUNDINGS AND HANGS

See Attachment II.

#### I. GENERAL NOTES

Morning and evening calibrations were made by running a range off the Fort Pierce Entrance Channel. (See Attachment I).

In addition to morning and evening calibrations, frequent lane counts were taken whenever practical on navigation buoys.

Throughout this survey an 800 ft. towline was utilized; thus the distance from the Raydist antenna to the end buoy was 265 meters.

The following occurrences should be noted when verifying this survey:

B DAY (21 March 1973)

Day was spent running ship hydrography over Item B3 and determining locations of parts of badly broken up wreck.

#### C DAY (22 March 1973)

Portion of day was spent running ship hydrography over Item B1 in an attempt to determine shoalest broken-up section of wreck. "Progress hampered by large ground swells originating to the northeast of the working area. This, combined with drag tender trouble, resulted in poor tests for the day.

#### D DAY (23 March 1973)

Large ground swells, originating to the northeast of the working area, again resulted in poor tests.

#### E DAY (27 March 1973)

Strip rejected for lack of tests due to launch trouble.

#### J. CURRENTS

In general, currents were from the North. However, it was found to be advantageous to conduct our own "current survey" prior to planning a strip. This was accomplished by setting a tester to the approximate depth of the drag, plotting its position as it entered and again as it was retrieved from the water and noting the length of time involved. In this manner both velocity and direction of the current were determined.

K. DISCREPANCIES AND COMPARISONS WITH RECENT SURVEYS AND CHARTS

In accord with Page 3, Paragraph 2 of Project Instructions, prominent

new landmarks were located, charted landmarks were re-evaluated, and a

letter sent to Coast Pilot Branch. See Attachment IX.

In general, charted depths from the most recent charts were found to be quite reliable, and were used daily in conjunction with hydrographic surveys supplied by AMC and ship hydro run immediately prior to wire dragging.

The following obstructions were located while searching for the charted items as provided for in Project Instructions and constitute discrepancies to existing charts.

- 1) The wreck near buoy "WR12A" at Lat. 27°23.6'N, Long. 80°03.1'W charted as cleared to 42 feet: the shoalest depth on the wreck a large hang at 65 pis. in 10° 27'23.5 ling. 80°03.7 metal hull, badly broken up was 65 1/2 feet. (Using predicted tides), at M.L.W. (See Review Par 4 item B-1)
- 2) The wreck charted at Lat. 27°20.2'N, Long. 80°04.6'W with a depth of 24 feet: the wreck, again a large metal hull badly broken up, was cleared to a minimum effective depth of 46 feet at M.L.W. (using pre-

#### L. PERSONNEL AND EQUIPMENT

Throughout this survey the RUDE & HECK acted as guide and end vessel respectively. Both ships are equipped with Raytheon DE-723 fathometers which were used in planning the drag strips. Ship's launches and skiffs alternated as drag tester units, dependent on the state of the sea and the weather.

Standard wire drag equipment was used throughout the survey. It should be noted that during the 1972-73 inport period, some "new" intermediate buoys were obtained. These buoys were left over from the old drag boats WAINWRIGHT & HILGARD and appear to be the same as our standard intermediate buoys: However, some question exists as to the weight and towing characteristics.

Officers aboard during this survey included: CDR L.E. Pickens, LCDR W.M. Noble, LTJG S.H. Manzo, LTJG B.L. Wescott, ENS H.B. Arnold, ENS R.D. Wells, and ENS T.A. Bergner.

#### M. MISCELLANEOUS

Operations were hampered by launch breakdowns and heavy swells originat— ing to the northeast of the working area. The heavy swell resulted in accepting a larger combined lift and swell than normal, and thereby reducing effective depths achieved.

#### N. SUMMARY

#### Item B-1

at Lat. 27°23.6'N, Long. 80°03.1'W, was cleared to 42 feet. The shoalest depth on the wreck - a large metal hull, badly broken up - was 65 1/2 feet (using predicted tides) at M.L.W. See Review Hung at 73 665

#### Item B-2

Due to time limitations, this item was not investigated. The priority assigned showed this item to be 3 or 4 of 4. Hydrography supplied by AMC indicated a shoal in the vicinity of Buoy "R12" as having a lesser

depth than that of the charted wreck.

Item B-3

Reposition 120 m wsw See Review

A charted wreck at Lat. 27°20.2'N, Long. 80°04.6'W. The wreck, with a charted depth of 24 feet, was located using ship hydrography in conjunction with a previous hydrographic survey. The wreck, a large metal hull again badly broken up, was cleared to a minimum effective depth of 46 feet using predicted tides.

#### RECOMMENDATIONS

Recommend Item B1 be charted as cleared to 65 feet. This item is considered complete. Not considered complete

Recommend Item B2 be given additional work.

Recommend Item B3 be charted as cleared to \$6 feet. This item is considered complete.

#### APPROVAL SHEET

All records of this survey prior to smooth plotting are hereby approved. Item B2 was not investigated due to time limitations in the area. The priority assigned showed this item to be 3 or 4 of 4. Hydrography supplied by AMC indicated a shoal in the vicinity of buoy "R12" as having a lesser depth than that of the charted wreck. Items B1 and B3 are considered complete and adequate for charting. The field work was personally supervised by the undersigned and the boatsheet and records were inspected daily.

Commanding Officer
NOAA Ships RUDE & HECK

#### LIST OF ATTACHMENTS

ı.	A) RAYDIST CONTROL STATIONS B) VISUAL CONTROL SIGNALS
II.	LIST OF GROUNDINGS AND HANGS
III.	A) DAILY RAYDIST CORRECTORS B) ELECTRONIC CALIBRATION INFORMATION
IV.	STATISTICS
v.	AIDS TO NAVIGATION
	PROJECT INSTRUCTIONS A) CHANGE #1 B) CHANGE #2 C) CHANGE #3
VII.	RAYDIST STATION DESCRIPTIONS
VIII.	A) TIDES, SMOOTH B) REPORT - TIDE STATION
IX.	COAST PILOT CHANGES
х.	PARAMETERS A) BOATSHEET, REQUEST FOR B) ELECTRONIC CONTROL PARAMETER SHEET

#### ATTACHMENT I

Α.	TAYDT ST	CONTROL.	STATIONS
Λ.	NUTDIDI	OONTIOD	DIVITORD

station	lattitude	longitude	remarks
FAT	27 34 38.629	80 19 38.080	RED STATION
WORTH	26 57 37.855	80 05 02.040	GREEN STATION
В.	VISUAL CONT	ROL SIGNALS	
signal	lattitude	longitude	remarks
PIERCE 2	27 28 11.217	80 17 27.9	FRONT RANGE
TANK	27 27 23.520	80 19 44.1	REAR RANGE
J.C. PARK TANK	27 27 10 <b>.</b> 160	80 17 13.3	LEFT ANGLE

<sup>\*</sup> NOTE: Pierce 2 was a visual signal constructed by ship's personnel over the disc of the same name. The structure was approximately 25 feet tall.

ATTACHMENT II

E ' · E

(C)4 (3/20

## LIST OF GROUNDINGS AND HANGS

Position No. & Dayletter	Buoy No.	Lattitude	Longitude	Grounded Effective Depth	Cleared by Day &	Cleared Effective	Charted	
			Hongroude	Charles and the second	Strip No.	Depth	Depth	Remarks
13-A	3-4	27 23.48	80 03.62	75	C-3	71 reject	ed 56	Hung "Amazone" S.to N.
20 <b>-</b> C	2-3	27 23.43	80 03.38				105	Hung "WR12A" keeper buoy from N. to S.
20-C3	3-4	27 23.45	80 03.15		<u>-</u>		105	Hung "WR12A" buoy from N. to S.
9-D	2-3	27 23.43	80 03.38		<u></u>		105	Hung "WR12A" keeper buoy from S. to N.
9-D	3-4	27 23.45	80 03.15				105	Hung "WR12A" buoy from S. to N.
19 <b>-</b> D	2-3	27 23.48	80 03.62	75	D-2 -C-3	Not cleared	56	Hung "Amazone" from N. to S.
DP 6-E	3-4	27 20.2	80 04.6	54			24	Item B-3. Strip rejected, but saved hang location.
28 <b>-</b> F	3-4	27 20.15	80 04.55	50	F-2	45-	24	Rehung Item B-3

ATTACHMENT III

### DAILY RAYDIST CORRECTORS

		RUDE		HEC	K
date	day letter	red g	reen	red	green
19 March 1973	A	+0.2	0.0	-0.1	-0.1
21 March 1973	В		Recon.	Hydro	
22 March 1973	C	+0.2 +	0.2	+0.1	-0.1
23 March 1973	D	+0.2 +	0.2	+0.1	-0.1
27 March 1973	E		Rejec	eted	
28 March 1973	F	0.0	0.0	-0.1	-0.2

### ATTACHMENT IV

#### STATISTICS

	date	day letter	strip #	volume #	positions	L.N.M.	S.N.M.
19	March 1973	А	1	Ţ	13	1.15	1.15
21	March 1973	В		R	econ. Hydro -		
22	March 1973	C	1	I	14	2.0	1.8
		C	2	I	6	0.3	0.23
	· /	C	3	I	10	1.20	1.02
23	March 1973	D	1	I	9	1.20	0.83
	•	D	2	I	10	1.0	0.45
	•	D	3	I	10	1.0	0.50
27	March 1973	E	1	I	F	Rejected	
28	March 1973	. F	1	. I	12	1.27	0.93
		F	2	II	10	1.15	0.80
		F	3	II	6	0.70	0.49

### ATTACHMENT V

### FLOATING AIDS TO NAVIGATION

name	lattitude	longitude	remarks	<del></del>
Buoy "10A"	27 26.55	80 13.45	Used to check lane	e count.
Buoy R"12"	27 23.18	80 07.65	Used to check lane	
Buoy R"WR12A	" 27 23.45	80 03.15	Used to check lane	count.
Keeper Buoy for R"WR12A"	27 23.43	80 03.38	Used to check lane	e count.

## ATLANTIC MARTHE CENTER

## ELECTRONIC CONTROL PARAMETERS

SP-AMC-1 1. Project #-OPR-		3. Field # RH-20-2-73 WD
4. Type of Contro	1 Raydist	(Hi-Fix, Raydist, EPI, etc.)
5. Frequency 330	(for conv	ersion of electronic lanes to meters
6. Mode of Operat	ion (check one):	
Range-Range		Range-Visual
Range, Two	1.D. FAI	Lat. 27 ° 34 '38.629" Long. 80 ° 19 '38.629" Lat. 26 ° 57 '37.855" Long. 80 ° 05 '02.040"
Hyperbolic (	3-station)	Hyper-Visual .
Slave One Station Master Station Slave Two Station	I.D.	Lat. Long.  Lat. Long.  Lat. Long.  Lat. Long.  Lat. Long.
7. Location of Su	rvey:	
Range-Range		server is standing at $R_1$ Station and tly at $R_2$ (check one):
	Survey area	is to observer's Right A=Ø
	Survey area	is to observer's Left A=1
Hyperbolic	Looking from	survey area toward Master Station:
		ust be to observer's Left.
		ust be to obscrver's Right.
This form	is submitted as an	aid in preparing a boat sheet.
This form	applies to all data	on this survey.
This form	applies to part of	the data on this survey.
Vessel EDP #	From Time Day	To Position Numbers Time Day (inclusive)
Pa		to to to
9. Remarks: R	1 RED , F	22 BIUE

## ATLANTIC MARINE CENTER

## PROJECTION PARAMETERS

## POLYCONIC OR MODIFIED TRANSVERSE MERCATOR

1.	Project No. SP-AMC-1-R/H-73 4. Requested By M W Johnson								
	Reg. No. H-948 5. Ship or Office Verification								
3.	Field No. R/H-20-2-73 6. Date Required asap								
7.	Polyconic Modified Transverse Mercator x								
	Central Meridian of Projection 080 ° 08 ' 00 "								
9.	Survey Scale: 1:20,000								
10.	Size of Sheet (check one):								
	36 x 54 36 x 60 Other x Specify 36"X36"								
11.	Sheet Orientation (check one):								
	$NYX = 1   NYX = \beta   X$								
	· N								
	No.								
	CHEED								
	CMER								
12	. Plotter Origin: S.W. Corner of Sheet (not necessarily a grid								
	Latitude 27 ° 18 ' 00 " intersection)								
	Longitude 080 ° 12 '00 "								
1.3	13. G.P.'s of triangulation and/or signals attached x								
14	. Material Desired: Tracing Paper Mylar								
	Smooth Sheet X Other Specify A&D sheet .003 mylar								
15	. Remarks: Smooth sheet type grid and Raydist arcs								
	A&D sheet, tick marks only								

#### ADDENDUM

#### H-9000 WD SP-AMC-1-RH-73

Item Bl (wreck "Amazone", 27°23.48', 80°03.62') of H-9368 WD was hung on A Day Strip l with an effective depth of 73 feet. Strip 2 of A Day also hung this item. The strip was not used, but the approximate effective depth was 69 feet. C Day Strip 3 cleared with an effective depth of 70 feet. Day Strip 2 hung this item with an effective depth of 65 feet. We were unable to resolve this discrepancy. This item is shown on the smooth sheet and A&D sheet as hung at 65 feet with no cleared depth.

It appears that this survey proves only that a wreck does exist at this location.

Norfolk, Virginia November 14, 1974 W. L. Jonns
Chief, Verification Branch
Processing Division
Atlantic Marine Center

## ATLANTIC MARINE CENTER APPROVAL SHEET FOR

## AUTOMATED SURVEY H-9568 WD SP-AMC-1-RH-73

A. All revisions and additions made on the smooth sheet during verification have been entered in the magnetic tape records for this survey. A new final position printout has/has not been made. A new final sounding printout has/has not been made. NA

Date: November 14.1974

Signed:

williamotoms

Title:

William L.Jonns Chief, Verification Branch

B. The verified smooth sheet has been inspected, is complete, and meets the requirements of the Hydrographic and AMC Manuals. Exceptions are listed in the verifier's report.

Date: November 14,1974

Signed:

Dale North Jr. LCDR NOA

Title:

Chief, Processing Division

NOAA FORM 76-155 (11-72)	N A	TIONAL	OCEANIC				OMMERCE STRATION	SU	RVEY N	UMBER	
	GEC	GRAPH	IIC NA							1974 W	.D.
Name on Survey		/A°	IN CHART H	o. Con	U.S. MAPS	ANGLE ON LOCAL ON LOCAL ON LOCAL ON LOCAL	OH MAE	o. Guide	OR MAP	,s.Light V	51
											1
											2
											3
											4
											5
***************************************											6
•	,										7
-											8
	2 20 11 11										9
											10
											11
											12
						. +					13
						,					14
											15
											16
											17
	;										18
								1			19
											20
											21
											22
											23
											24
											25

NOAA FORM 77-27 (9-72) (PRESC BY HYDROGRAPHIC MANUAL 20-2. 6-94 7-13)

# HYDROGRAPHIC SURVEY NO. #1-9368 F.E.No.2-1974 W.D. SP-AMC-1-RH-73

RECORDS ACCOMPANYING SURVEY: To be completed when survey is registered.

RECORD DESCRIPTION			AMOUNT			RECORD DESCR	AMOUNT		
smooth sheet & A&D Sheet			1		BOAT S	HEETS		20	
DESCRIPTIVE RI	DESCRIPTIVE REPORT			l overlays					
DESCRIPTION	DEPTH RECORDS	HORIZ.	CONT. PRIN		TOUTS TAPE ROLLS F		PUNCHED CARDS	ABSTRACTS/ SOURCE DOCUMENTS	
ENVELOPES									
CAHIERŠ	*							*	
VOLUMES	1	3 wi	re dr	9.5					
BOXES						*		1	
T-SHEET PRINTS	T-SHEET PRINTS (List)								

SPECIAL REPORTS (List)

na

OFFICE PROCESSING ACTIVITIES

The following statistics will be submitted with the cartographer's report on the survey

	AMOUNTS				
PROCESSING ACTIVITY	PRE- VERIFICATION	VERIFICATION	REVI	EW TQTALS	
POSITIONS ON SHEET				200	
POSITIONS CHECKED		40			
POSITIONS REVISED		7			
DEPTH SOUNDINGS REVISED					
DEPTH SOUNDINGS ERRONEOUSLY SPACED					
SIGNALS ERRONEOUSLY PLOTTED OR TRANSFERRED		Elec Control			
		TIME (MANHOURS)			
TOPOGRAPHIC DETAILS		0			
JUNCTIONS		0			
VERIFICATION OF SOUNDINGS FROM GRAPHIC RECORDS		0			
SPECIAL ADJUSTMENTS		0	1		
ALL OTHER WORK	2	51	26		
TOTALS	2	51	20		
PRE-VERIFICATION BY Johnnie Griffin				Oct.24,74	
Michael Johnson		Nov.1,74 Nov		Nov.12,74	
D D Romesters				12-16-74	

lneg. 7, B. Pewers 2028-75 11 for cardlen 13 4 U.S. G.P.O., 1972-769-562/439 REG.#6

#### REVIEW

## FIELD EXAMINATION NO. 2, 1974 W.D. WIRE-DRAG INVESTIGATIONS FLORIDA EAST COAST, FORT PIERCE INLET, OFF ST. LUCIE SHOAL

- 1. This wire-drag field examination was made in compliance with Project Instructions SP-AMC-1-R/H-73, dated January 15, 1973.
- 2. The purpose of the field examination was to investigate the three wrecks reported offshore of Fort Pierce in lat. 27°23.6', long. 80°03.1'; lat. 27°23.0', long. 80°08.0' and lat. 27°20.2', long. 80°04.6'. Wreck buoys marking two of these items may be discontinued by the Coast Guard pursuant to information from the wire-drag investigations.
  - 3. The results of the investigation are shown on the accompanying Mylar overlay inserted in the Descriptive Report.
  - 4. A comparison between Chart 1247 and the field examination indicates that the following revisions to the chart are necessary to reflect the final results of the investigations:
    - A. The cleared by 42 Wk charted in lat. 27°23.6', long. 80°03.2' from F.E. No. 5 of 1944 was disproved by an effective drag of 84 feet on the field examination and should be deleted from the chart. The 56 Wk charted in lat. 27°23.5', long. 80°03.7' from H-8783 (1964) is believed to be the same wreck and should be retained on the chart.


Verification of the location of the wreck at the position of the 56 Wk was obtained with a hang of 65 feet on the field examination. This hang was not cleared by subsequent drag strips and therefore should not supersede the 56 Wk for charting.

B. The 24 Wreck charted in lat. 27°20.2', long. 80°04.62' was located on H-8957 (1967). The wreck was hung at 49 ft. and cleared at 45 ft. on the present field examination. It should be charted in accordance with present information.

- 5. The wreck in paragraph 4B was cleared twice from one direction and observed by divers.
- 6. The wreck at lat. 27°23.5', long. 80°03.7' (para. 4A) was not satisfactorily investigated. It was hung on A day at 73 feet and later cleared by 70 feet the same day. The 70 ft. cleared depth has been rejected. On D-day, the wreck was hung again at 65 feet without being cleared by subsequent drag strips. Divers estimated the wreck to extend 25-30 feet off the bottom in depths of 80-85 feet. Fathograms show wreck traces to 62 feet. Additional work on this item at some future date should be done to resolve this conflicting data.
- 7. Drag work was accomplished on several days when the sea and swell were 5 and 6 feet which is excessively large and undoubtably contributed to the questionable data obtained on these investigations. Depth observations by divers was also questionable and some has apparently been rejected in the field.
- 8. The Descriptive Report adequately covers all other matters pertinent to this examination. No further discussion is considered necessary.


Reviewed by: D. J. Romesburg
December 16, 1974


Inspected by: F. B. Powers February 28, 1975





27° 19

80 03









#### NAUTICAL CHART DIVISION

#### **RECORD OF APPLICATION TO CHARTS**

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. F.E.No. 2-1974 W.D.

#### INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

1. Letter all information.

2. In "Remarks" column cross out words that do not apply.

3. Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Revi

CHART	DATE	CARTOGRAPHER	REMARKS.
411	10-31-86	Daylie P	Full Pare Before After Verification Review Inspection Signed Via
	•	٦	Drawing No. 60
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
		,	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
		•	Drawing No.
		·	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			<b>.</b>
		. 1	Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No. /
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
. —			